

Corrigendum

With reference to the tender uploaded on 21-08-2015 vide refer No- SIC/HO/WD/1(XXXiV)/04 for "Renovation/ modification work of drainage system of NSIC exhibition Ground, Okhla Industrial Estate, New Delhi -110020". Please read Page No 34 as per enclosed Page here with.

	female coupling by SS wire on every 30 meter length.					
				Total of A		
B.	Construction of water harvesting pit					
1	Earth work in excavation by Mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm. in depth , 1.5 m in width as well as 10 Sqm. On plan) including disposal of excavated earth load upto 50 m and lift upto 1.5 m disposed earth to br leveled and neatly dressed for all kind of soil.	Cum	54.473			
2	Earth work in excavation by Mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm. in depth , 1.5 m in width as well as 10 Sqm. On plan) including disposal of excavated earth load upto 50 m and lift upto 1.5 m disposed earth to br leveled and neatly dressed for ordinary rock.	Cum	68.880			
3	Extra for every additional lift of 1.50 m. or part thereof in excavation/banking excavated or stacked materials- Ordinary or hard rock.	Cum	86.100			