

SIC/WD/(XXXIV)/04

Dated 7-8-2009

To

**Subject- Quotation for P/f Front Lit Flex hoardings boards at NSIC
Complex Okhla Industrial Estate, New Delhi.**

Please find enclosed herewith schedule of quantities (Annexure-“A”) for the subject work. You are requested to quote your competitive rates against each item mentioned on schedule of quantities enclosed herewith on the terms and conditions mentioned below.

Scope of work:

1. Fabrication and Fixing of MS structure for display of flex of size 40’x10’-2 nos. and 20’x10’- 2 nos. as per approved design and enclosed drawing for display of front lit flex boards. The total height of the structure from Ground Level shall be 20 ft. The main structure along with its support should be fabricated and installed as per the drawing enclosed herewith and to the satisfaction of Engineer-in-charge.
2. Providing and fixing of flex signage’s boards of approved back ground matter and design supported with 2”x2” tubular section structure and front lit metal halide as per direction of Engineer In charge.

Terms and conditions:

1. Material of approved quality/make and shade shall only be accepted.
2. All the materials have to be approved by the Engineer-in-charge before finalization. All above dimensions are approximate and may change as per requirement and instructions of Engineer In-charge.
3. Rate should be inclusive of the cost of materials, fabrication, scaffolding, grouting, fixing, cartage, transportation labours, T & P and taxes etc. complete in all respect.

4. Payment will be released by Cheque after satisfactory completion of the work on actual measurement basis. All statutory deductions as applicable shall be deducted from your payable amount.
5. Technical specification for fabrication of structure and installation of flex has to be followed as mentioned in Annexure "A".
6. Work should be completed within twenty (20) days from the date of acceptance of work order. In case work is not completed within schedule time liquidated damages @ 0.5 % (half percent) per day shall be charged.
7. All the bidders are advised to visit the site for assessing the site condition before quoting the rates.
8. Power supply for installation of structure as well as for installation of lights shall be provided by NSIC at nearest available point. However, necessary wiring, cabling, conducting etc. in accordance with IS/ relevant codes of practice shall be the responsibility of the successful bidder.

Your offer should reach this office on 21st August 2009 by 3 PM. Offers shall be opened on the same day at 3.30 PM.

Thanking you,

Yours faithfully

M. A. Khan
Chief Manager (Works)

Annexure-“A”

Schedule of quantities

| S.no. | Description of item | Qty | Rate (Rs.) | Amount (Rs.) |
|-------|---|----------------|------------------|------------------|
| 1. | MS Structure work in welded built up section including installation in position finishing, cutting, hoisting fixing in position- etc. complete in all respect for fixing the hoarding frame of required size as per drawing enclosed and as per direction of Engineer in-charge. | 3858 Kg. | | |
| 2. | Excavation for grouting and fixing of frame structure | 3.45 Cum. | | |
| 3. | P/l in position CC of 1:2:4 grade for fixing of MS structure for signage board | 3.45 Cum. | | |
| 4. | P/f GI sheet of 22 gauge for supporting wind pressure on MS structural frame. | 1200 Sqft. | | |
| 5.. | P/f front lit flex Signage Board of approved back ground and matter made of flex and fixed over 2”x2” MS tubular structure. Spacing of MS tubular section shall not be exceed 3’ in each direction including fabrication fixing, painting -- etc. complete in all respect. (Note- Base MS supporting structure shall be provided by the Corporation) | 1200 Sq.ft. | | |
| 6. | P/F of front lit metal halide of 250 watt each of approved make, fixed with proper clamp, wiring and switches over flex hoarding for proper lighting at specified spacing as per direction of Engineer In-charge. | 16 Nos. | | |
| | | | Total Rs. | |

Total quoted amount in words-----

Signature of bidder with stamp

Annex B.

