

Dated 26-8-2009

Го	

Subject- Quotation for P/f Front Lit Flex hoardings boards at NSIC Complex Okhla Industrial Estate, New Delhi.

Please find enclosed herewith schedule of quantities (Annexure-"A") for the subject work. You are requested to quote your competitive rates against each item mentioned on schedule of quantities enclosed herewith on the terms and conditions mentioned below.

Scope of work:

- 1. Fabrication and Fixing of MS structure for display of flex of size 40'x10'-2 nos. and 20'x10'-2 nos. as per approved design and enclosed drawing for display of front lit flex boards. The total height of the structure from Ground Level shall be 20 ft. The main structure along with its support should be fabricated and installed as per the drawing enclosed herewith and to the satisfaction of Engineer-in-charge.
- 2. Providing and fixing of flex signage's boards of approved back ground matter and design supported with 2"x2" tubular section structure and front lit metal halide as per direction of Engineer In charge.

Terms and conditions:

- 1. Material of approved quality/make and shade shall only be accepted.
- 2. All the materials have to be approved by the Engineer-in-charge before finalization. All above dimensions are approximate and may change as per requirement and instructions of Engineer In-charge.
- 3. Rate should be inclusive of the cost of materials, fabrication, scaffolding, grouting, fixing, cartage, transportation labours, T & P and taxes etc. complete in all respect.

- 4. Payment will be released by Cheque after satisfactory completion of the work on actual measurement basis. All statuary deductions as applicable shall be deducted from your payable amount.
- 5. Technical specification for fabrication of structure and installation of flex has to be followed as mentioned in Annexure "A".
- 6. Work should be completed within twenty (20) days from the date of acceptance of work order. In case work is not completed within schedule time liquidated damages @ 0.5 % (half percent) per day shall be charged.
- 7. All the bidders are advised to visit the site for assessing the site condition before quoting the rates.
- 8. Power supply for installation of structure as well as for installation of lights shall be provided by NSIC at nearest available point. However, necessary wiring, cabling, conducting etc. in accordance with IS/ relevant codes of practice shall be the responsibility of the successful bidder.
- 9. Bidders who have applied against earlier offer dated 7-8-2009 should also submit their offer again afresh.

Your offer should reach this office on 2nd September 2009 by 3 PM. Offers shall be opened on the same day at 3.30 PM.

Thanking you,

Yours faithfully

M. A. Khan Chief Manager (Works)

Annexure-"A"

Schedule of quantities

S.no.	Description of item	Qty	Rate	Amount
			(Rs.)	(Rs.)
1.	MS Structure work in welded built up	3858		
	section including installation in position	Kg.		
	finishing, cutting, hoisting fixing in			
	position- etc. complete in all respect for			
	fixing the hoarding frame of required			
	size as per drawing enclosed and as per			
_	direction of Engineer in-charge.			
2.	Excavation for grouting and fixing of	3.45		
	frame structure	Cum.		
3.	P/l in position CC of 1:2:4 grade for	3.45		
	fixing of MS structure for signage board	Cum.		
4.	P/f GI sheet of 22 gauge for supporting	1200		
	wind pressure on MS structural frame.	Sqft.		
5.	P/f front lit flex Signage Board of	1200		
	approved back ground and matter made	Sq.ft.		
	of flex and fixed over 2"x2" MS tubular			
	structure. Spacing of MS tubular section			
	shall not be exceed 3' in each direction			
	including fabrication fixing, painting			
	etc. complete in all respect.			
	DE CC 412 411 121 COCO	1.6		
6.	P/F of front lit metal halide of 250 watt	16		
	each of approved make, fixed with	Nos.		
	proper clamp, wiring and switches over			
	flex hoarding for proper lighting at			
	specified spacing as per direction of			
	Engineer In-charge.		Total Da	
			Total Rs.	

Total quoted amount in words-----

Signature of bidder with stamp

