

SIC/HO/STP/Misc.maint./1(55)/105

Date – 29-4-2013

To,

M/s

Subject: Quotation for misc. maintenance works at NSIC STP Extension:

Please find enclosed here with Performa for schedule of quantities for the subject work at NSIC STP Extension building, Okhla Industrial Estate, New Delhi-110020. You are requested to quote your competitive rates against each item mentioned in schedule enclosed with at the terms and conditions given below...

1. Rates should be inclusive of the cost of materials, labours, fixing, cartage, transportation, scaffolding, other T&P and taxes etc. in all respect.
2. Materials, fixtures and fittings of approved quality / make as specified in the schedule shall only be accepted.
3. Payment will be released by cheque after satisfactory completion of the work on actual measurement basis.
4. All statutory deductions as applicable shall be deducted from your payable amount.
5. Work should be completed within 20 days from the date of acceptance of work order.
6. All the bidders are advised to visit the site for assessing the site condition before quoting the rates.
7. Offer should reach to this office up to 8th May 2013 by 3.00 PM. Offers shall be opened on the same day at 3.30 PM.

Thanking You.

Yours faithfully

M.A. Khan
Chief Manager (Works)

Estimate for Renovation of STP Extension					
S. No.	Description of item	Qty	Unit	Rate (Rs.)	Amount (Rs.)
1	Replacement of damaged Armstrong false ceiling tiles of size 2'x2' in STP ext. entrance including removal of damaged tiles and fixing of new tiles and disposal of malba within a lead of 50 meter.	1052.00	Sqft		
2	Replacement of damaged vitrified floor tiles including removal of old damaged tiles and fixing of new vitrified tiles of size 600 mm x600 mm and 9 mm thick of Kajaria, somani or marbonite make with water absorption less than 0.08% and conforming to IS :15622 of approved make in all colours and shade laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand) including grouting the joints with white cement and matching pigment etc. complete with disposal of malba within a lead of 50 meter.	50.00	Sqft		
3	Painting walls with oil bond washable distemper of Berger, Ashian or ICI make and of approved colour and shade as per manufacturers specifications with two or more coats to give an even look.	3000.00	Sqft.		
4	Painting grill and railing with synthetic enamel paint of Berger, Ashian or ICI make and of approved colour and shade as per manufacturer's specifications with two or more coats to give an even look.	200.00	Sqft		
5	Waterproofing of Chhajja with waterproof cement concrete of 1:2:4 (1 Cement :2 coarse sand : 4 graded stone aggregate 12 to 20 mm) with water proofing compound.	1.00	Cum		
				Total	

Total in words-----

Signature of bidder with stamp

