

NTSC/OK/CM/12/2010-11

Dated 25-11-2010

**Sub: Quotation for renovation of Conference room at NTSC Okhla .**

Dear Sir,

This has reference to our offer letter vide no. NTSC/OK/CM/12/2010-1 Dated 11-11-2010.

It has been observed that there is typographical error in the schedule of quantities which were sent earlier with our letter dated 11.11.2010; the same may be treated as null and void.

Further, enclosed please find .herewith the revised schedule of quantities with a request to quote your competitive rates against each items mentioned in the revised schedule of quantities.

In view of the correction in the revised schedule of quantities, the last date for submission of offer is extended from 29<sup>th</sup> November 2010 to 15<sup>th</sup> December, 2010.

Your bid shall reach to this office by 15<sup>th</sup> December 2010 by 3 PM. Offer shall be opened on the same day at 3.30 PM.

All the other terms and conditions shall remain unchanged as communicated through our letter No. NTSC/OK/CM/12/2010-11 Dated 11-11-2010.

Yours faithfully,

**(Satvinder Singh)**  
General Manager

Enclosure: Revised Schedule of Quantities (Total pages three including the above covering letter)

### Revised Schedule of Quantities

S.no.	Description of item	Qty	Rate ( Rs.)	Amount ( Rs.)
1.	Dismantling of aluminum partitions and brick work. i) Existing walls, aluminum partitions and window room size 14'x17'	528 Sq.ft.		
2.	P/f of 9 MM thick vitrified tiles of Ivory white of size 2'x2' of the Marbonite or equivalent make fixing with fixing chemical. i) In Floor ii) In skirting	238 sq.ft 10 sq.ft Total: 248 Sq.ft		
3.	Supply and fixing of Armstrong make false ceiling Adore micro look tiles with silhouetted grid system having NRC 0.5 and RH 95 of approved shade and design.	238 Sqft.		
4.	Supply and fabrication of full height powder coated Aluminum glazed partitions for cabins and doors with tubular powder coated Aluminium section of size 2" x2" including p/f of necessary fittings including locks, handle, tower bolts, beading rubber etc. complete in all respect.	432 Sqft.		
5.	P/f of heavy duty floor spring in glass doors.	1 no.		
6.	Providing and applying of Heritage paint on walls.	162 Sqft.		
7.	P/f of sun control film on partitions and doors. on glass partitions on windows.	432 Sq.ft. 45 Sq.ft Total: 477Sq.ft		

8.	P/f of roller blinds on windows.	7.00 Sqm.		
9.	P/f light fixtures of approved make and design of 2'x2' size for false ceiling.	6 Nos.		
10.	Labour charges for fabrication of GI sheet roofing with framed structure( Old GI sheet is available in our office and may be inspect by bidder before submission of offer)	238 Sqft.		
			<b>Total (Rs.)</b>	

**Total Rs. in words** -----

-----

**Signature of bidder with stamp**