

SIC/HO/STP/MISCMINT./1(55)/05

Date – 5-1-2009

To,
M/s

Subject : Quotation for renovation of toilet block at NSIC STP:

Please find enclosed here with Performa for schedule of quantities for the subject work at NSIC STP building, Okhla Industrial Estate , New Delhi-110020. You are requested to quote your competitive rates against each item mentioned in schedule enclosed with at the terms and conditions given below..

1. Rates should be inclusive of the cost of materials, labours, fixing, cartage, transportation , scaffolding, other T&P and taxes etc. in all respect.
2. Materials , fixtures and fittings of approved quality / make as specified in the schedule shall only be accepted.
3. Payment will be released by cheque after satisfactory completion of the work on actual measurement basis.
4. All statutory deductions as applicable shall be deducted from your payable amount.
5. Work should be completed within 30 days from the date of acceptance of work order . In case work is not completed within schedule time liquidated damage @ 2% per week shall be charged..
6. The bidders along with their offer should submit earnest money of Rs. 10,000/- in the form of Demand draft in favour of “National Small Industries Corporation Ltd New Delhi”.
7. Earnest money of unsuccessful bidder (Other than the lowest bidder) shall be returned after opening of price bids and earnest money of successful bidder shall be retained as security deposit till the successful completion of the work
8. All the bidders are advised to visit the site for assessing the site condition before quoting the rates.
9. Offer should reach to this office up to 13th January 2009 by 3.00 PM . Offers shall be opened on the same day at 3.30 PM.

Thanking You.

Yours faithfully

M.A. Khan
Chief Manager (Works)

Schedule

S N.	DESCRIPTION	UNIT	QTY	RATE (RS)	AMOUNT (RS)
1.	Providing and applying POP putty of 2mm thick over plastered surface to prepare the surface even and smooth.	Sqm	70.00		
2.	Wall painting with two or more coats on old work with texture paint of approved brand and manufacture to give an even shade etc. complete as per direction of Engineer-In-Charge	Sqm	70.00		
3.	French spirit polishing on wood work (one or more coat) on new wood work.	Sqm	4.0		
4.	Providing and laying anti skid ceramic floor tiles (thickenss as per manufacturer's specification) size-300 mm x 300 mm or more of 1st quality conforming to IS:15622 in all colours, shades of approved make of NITCO or equivalent make laid on floor using cement based high polymer modified quick-set tile adhesive (water based conforming to IS:15477 using 5 kg adhesive per sqm of tile area in avg. 3 mm thickness.as per direction of Engineer-In-Charge	Sqm	27.00		
5.	PCC of 1:4:8 (1 Cement:4 Coarse sand : 8 coarse aggregate) in base of floor.	Cum.	2.70		

6.	Providing and fixing 18 mm thick gang saw cut mirror polished (pre-moulded and pre-polished) machine cut Granite stone for wash hand basin of any colour and shade (area of slab over 0.5 sqm)laid over 20 mm thick base cement mortar (1:4) with joints treated with white cement mixed with matching pigment, epoxy touch ups including rubbing, cutting, moulding and polishing to edge to give high gloss finish etc. complete.	Sqm	2.50		
7.	Fixing granite stone over and above corresponding basic item, in facia and drops of width upto 150 mm with epoxy resin based adhesive including cleaning etc. complete	metre	6.10		
8.	Providing opening of required size and shape for wash basins in platform in granite stone work including necessary holes for pillar taps etc. including rubbing and polishing of cut edges etc. complete	each	3.00		
9.	Reinforced cement concrete work for wash hand basin platform excluding cost of shuttering, centering and reinforcement with 1:2:4 mix.	cum	0.30		
10.	TMT Reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete	Kg	30.00		
11	Centering and shuttering including strutting, propping etc. and removal of form for wash hand basin platform	Sqm	2.00		

12	Providing and laying 1st quality ceramic glazed wall tiles conforming to IS:15622 of approved make in approved colour and shade in wall dado over 12 mm thick bed of cement mortar 1:3 and jointing with grey cement slurry @3.3 kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	Sqm	125.00		
13	Providing wood work in frames of doors/windows and fixed in position etc. complete in all respect. (IInd class Teak wood)	Cum.	0.2		
14	Providing and fixing ISI MARKED flush doors (35mm TH) conforming to IS:2202(part-I) non-decorative type.	Sqm	8.00		
15	Providing and fixing glazed shutter for ventilator using glass(4mm TH.) with 2nd class Teak Wood (35mm TH.)	Sqm	2.00		
16	P/f hard drawn steel wire fabric 75x25 mm mesh of weigh not less than 7.75 kg per sqm to window frame including beading 62x19mm of second class teak wood.	Kg.	12.00		
17	Providing and fixing bright finish brass barrel/ tower/ socket bolt (full covered) of approved quality manufactured from extruded section conforming to with cadmium plated screw:				
	(1)250mm. long x10mm. dia. bolt	Each	4.00		
	(ii)200mm.long x10mm.dia. bolt.	Each	6.00		
18	Providing and fixing Chromium plated brass D-type handle of approved quality manufactured from extruded section confirming to I.S. specification complete:.				
	(ii)Size: 125 mm	Each	4.00		

19.	Supplying fitting and fixing Brass door stopper	Each	2.00		
20.	Providing and fixing IS:3564 marked Aluminium die cast body tubular type universal hydraulic door closer with necessary accessories and screws etc. complete.	Each	2.00		
21	Supplying fitting and fixing of " Godrej make mortice lock with latch and keys 6 lever including all complete.	Each	2.00		
	WATER SUPPLY & SANITARY WORKS				
22	Providing and fixing PVC sanitary pipe for sanitary.				
	100mm dia	Rmt	12.00		
	75mm dia.	Rmt	15.00		
23	Providing and filling joints in pipe				
	75mm dia.	Each	7.00		
	100mm dia	Each	4.00		
24	Providing and fixing Nahani trap.(100mm dia.)	Nos	6.00		
25	Supplying, fitting & fixing GI pipes TATA make (B class mediumg) with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbow ,nipple, long screw, reducing socket, reducing tees, short pieces etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting, fixing etc. complete in all respect include cost of all necessary fittings as required, jointing material and two coats of painting with approved paint in any position above ground. (payment will be made				

	on the center line measurement of the total pipe line . No separate payment will be made for accessories, specials.)				
	a)15mm nominal bore	Rmt	18.00		
	b)40mm nominal bore	Rmt	30.00		
26.	Providing and fixing in position 18 mm thick gang saw cut mirror polished (pre-moulded and pre-polished) machine cut Granite stone for urinal partition in single piece of any colour and shade (area of partition slab over 0.5 sqm) including rubbing, cutting, moulding and polishing to edge to give high gloss finish etc. complete as per direction of Engineer-In-Charge.	Sqm.	2.00		
27	Providing and fixing wall hanging European WC pan with "P" trap 100mm dia.(in colour) as per design & drawing and manufacturer's specifications.-580mm long (Make-Hindware, Parryware or equivalent) as approved by Engineer-In-Charge.	Nos	2.00		
28.	Providing and fixing in position flat back urinal pan with water sensor (in colour) as per design & drawing and manufacturer's specifications.- 510mm long (Make-Hindware, Parryware or equivalent) as approved by Engineer-In-Charge.	Nos	3.00		
29	Providing and fixing colour wash basin approx. size: 510 x 410 mm oval shape counter sunk as per design & drawing and manufacturer's specifications. (Make-Hindware, Parryware or equivalent) as approved by Engineer-In-Charge.	Nos	4.00		

30.	Providing and fixing Flush valve (make:Jaguar, Crabtree or any other equivalent make) for urinal as per design & drawing and manufacturer's specifications including all fittings etc. complete in all respects as approved by Engineer-In-Charge.	Each	2.00		
31.	Providing and fixing Bottle Trap (make:Jaguar, Crabtree or any other equivalent make) for urinal as per design & drawing and manufacturer's specifications as approved by Engineer-In-Charge.	Each	5.00		
32.	Providing and fixing C.P. Angular half turn cock (make:Jaguar, Crabtree or any other equivalent make) for basin as per design & drawing and manufacturer's specifications.	Each	4.00		
33.	Providing and fixing C.P. half turn angle valve (make:Jaguar, Crabtree or any other equivalent make) for urinal as per design & drawing and manufacturer's specifications as approved by Engineer-In-Charge.	Each	7.00		
34.	Providing and fixing Angular half turn C.P. bib cock (make:Jaguar, Crabtree or any other equivalent make) for urinal as per design & drawing and manufacturer's specifications as approved by Engineer-In-Charge.	Each	2.00		
35.	Providing and fixing Soap Dispenser (make:Jaguar, Crabtree or any other equivalent make) for urinal as per design & drawing and manufacturer's specifications.	Each	3.00		

36.	Supplying fitting , fixing "best quality" Mirror with silvering over plate glass 5.5 mm thick (Make-Modi / Saint Gobain or equivalent) fixed on wooden frame with Teak beadings complete in all respects (area of mirror - 32 sqft or above) as per direction of Engineer in charge.	Sqft	30.00		
37.	Providing and fixing C.P. hand shower foe W.C. (make:Jaguar, Crabtree or any other equivalent make) as per design & drawing and manufacturer's specifications as approved by Engineer-In-Charge.	Each	2.00		
38.	Providing and fixing in position CP Roller type paper holder of approved make.	Each	2.00		
39.	Misc. works (such as: Dismantling/ chipping out of old sanitary fittings and fixtures, floor/wall tiles, brick wall etc.)	L.S.			
			Grand total		

Total in Words: -----