

SIC/HO//ADMN-W/1 (XV)/03

Date – 29-10-2009

To,

M/s

Subject : Quotation for renovation of IInd floor toilet block:

Please find enclosed here with Performa for schedule of quantities for the subject work at NSIC Head office building, Okhla Industrial Estate , New Delhi-110020. You are requested to quote your competitive rates against each item mentioned in schedule enclosed with at the terms and conditions given below..

1. Rates should be inclusive of the cost of materials, labours, fixing, cartage, transportation , scaffolding, other T&P and taxes etc. in all respect.
2. Materials , fixtures and fittings of approved quality / make as specified in the schedule shall only be accepted.
3. Payment will be released by cheque after satisfactory completion of the work on actual measurement basis.
4. All statutory deductions as applicable shall be deducted from your payable amount.
5. Work should be completed within 45 days from the date of acceptance of work order . In case work is not completed within schedule time liquidated damage @ 2% per week shall be charged..
6. The bidders along with their offer should submit earnest money of Rs. 10,000/- in the form of Demand draft in favour of “National Small Industries Corporation Ltd New Delhi”.
7. Earnest money of unsuccessful bidder (Other than the lowest bidder) shall be returned after opening of price bids and earnest money of successful bidder shall be retained as security deposit till the successful completion of the work
8. All the bidders are advised to visit the site for assessing the site condition before quoting the rates.
9. Offer should reach to this office up to 9^h November 2009 by 3.00 PM . Offers shall be opened on the same day at 3.30 PM.

Thanking You.

Yours faithfully

M.A. Khan
Chief Manager (Works)

Schedule of work

S N.	DESCRIPTION	UNIT	QTY	RATE (RS)	AMOUNT (RS)
1.	Applying one coat of cement primer of approved brand and manufacture wall and ceiling surface	Sqm	35.00		
2.	Wall painting with two or more coats on old work with oil bond distemper paint of approved brand and manufacture to give an even shade etc. complete as per direction of Engineer-In-Charge	Sqm	35.00		
3.	French spirit polishing on wood work (one or more coat) on new wood work.	Sqm	7.00		
4.	Providing and laying anti skid ceramic floor tiles (thickness as per manufacturer's specification) size- 300 mm x 300 mm or more of 1 st quality conforming to IS:15622 in all colours, shades of approved make of NITCO or equivalent make laid on floor using cement based high polymer modified quick-set tile adhesive (water based conforming to IS:15477 using 5 kg adhesive per sqm of tile area in avg. 3 mm thickness as per direction of Engineer-In-Charge	Sqm	14.00		
5.	PCC of 1:4:8 (1 Cement:4 Coarse sand : 8 coarse aggregate) in base of floor.	Cum.	1.40		

6.	Providing and fixing 18 mm thick gang saw cut mirror polished (pre-molded and pre-polished) machine cut Granite stone for wash hand basin of any colour and shade (area of slab over 0.5 sqm)laid over 20 mm thick base cement mortar (1:4) with joints treated with white cement mixed with matching pigment, epoxy touch ups including rubbing, cutting, molding and polishing to edge to give high gloss finish etc. complete.	Sqm	2.00		
7.	Fixing granite stone over and above corresponding basic item, in facia and drops of width upto 150 mm with epoxy resin based adhesive including cleaning etc. complete	metre	3.60		
8.	Providing opening of required size and shape for wash basins in platform in granite stone work including necessary holes for pillar taps etc. including rubbing and polishing of cut edges etc. complete	each	2.00		
9.	Reinforced cement concrete work of 1:2:4 for wash hand basin platform excluding cost of shuttering, centering and reinforcement with 1:2:4 mix.	Cum	0.30		
10.	TMT Reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete	Kg	30.00		
11.	Centering and shuttering including strutting, propping etc. and removal of form for wash hand basin platform	Sqm	2.00		

12	Providing and laying 1 st quality ceramic glazed wall tiles conforming to IS:15622 of approved make in approved colour and shade in wall dado over 12 mm thick bed of cement mortar 1:3 and jointing with grey cement slurry @3.3 kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	Sqm	55.00		
13	Providing wood work in frames of doors/windows and fixed in position etc. complete in all respect. (1 st class Teak wood)	Cum.	0.123		
14	Providing and fixing ISI MARKED flush doors (35mm TH) conforming to IS:2202(part-I) non-decorative type.	Sqm	4.55		
15	Providing and fixing glazed shutter for ventilator using glass(4mm TH.) with 2 nd class Teak Wood (35mm TH.)	Sqm	0.74		
16	P/f MS grill of required size for ventilators	Kg.	50.00		
17	Providing and fixing bright finish brass barrel/ tower/ socket bolt (full covered) of approved quality manufactured from extruded section conforming to with cadmium plated screw:				
	(1)250mm. long x10mm. dia. Bolt	Each	2.00		
18	Providing and fixing Chromium plated brass D-type handle of approved quality manufactured from extruded section confirming to I.S. specification complete:.				
	(ii)Size: 125 mm	Each	4.00		
19.	Supplying fitting and fixing Brass door stopper	Each	1.00		

20	Supplying fitting and fixing of “ Godrej make mortice lock with latch and keys 6 lever including all complete.	Each	1.00		
	WATER SUPPLY & SANITARY WORKS				
21	Providing and fixing glazed SW pipe PVC sanitary pipe for sanitary.				
	100mm dia	Rmt	25.00		
22	Providing and fixing self cleaning trap (100mm dia.)	Nos	4.00		
23	Supplying, fitting & fixing GI pipes TATA make (B class medium) with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbow ,nipple, long screw, reducing socket, reducing tees, short pieces etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting, fixing etc. complete in all respect include cost of all necessary fittings as required, jointing material and two coats of painting with approved paint in any position above ground. (payment will be made on the center line measurement of the total pipe line . No separate payment will be made for accessories, specials.)				
	a)15mm nominal bore	Rmt	30.00		
24	Providing and fixing Indian type WC pan with “P” trap 100mm dia.(in colour) and flushing cistern as per design & drawing and manufacturer’s specifications.- 580mm long (Make-Hind ware, Parry ware or equivalent	Nos.	1.00		

25	Providing and fixing white vitreous wash basin approx. size: 550x400 mm oval shape counter sunk as per design & drawing and manufacturer's specifications. (Make-Hind ware, Parry ware or equivalent) as approved by Engineer-In-Charge.	Nos	2.00		
26..	Providing and fixing white vitreous china flat back half stall urinal of size 580x380x350 mm with white PVC automatic flushing cistern with fittings , standard size CP brass flush pipe , spreaders with unions and clamps (All in CP brass) with waste fittings as per IS 2556, CI trap including painting of fittings and making good the walls and floor of single half stall urinals with 5 liter PVC automatic flushing cistern.	Nos.	3.00		
27.	Providing and fixing Bottle Trap for washbasins as per design & drawing and manufacturer's specifications as approved by Engineer-In-Charge.	Each	5.00		
28	Providing and fixing C.P. half turn angle valve (make: Jaguar, Crabtree or any other equivalent make) for washbasins as per design & drawing and manufacturer's specifications as approved by Engineer-In-Charge.	Each	2.00		
29	Providing and fixing Angular half turn C.P. bib cock of 15 mm dia (make: Jaguar, Crabtree or any other equivalent make) .	Each	3.00		
30	Providing and fixing Soap Dispenser as per design & drawing and manufacturer's specifications.	Each	2.00		

31	P/f mirror of superior glass (of approved quality) and of required shape and size with plastic molded frame of approved make and shade with 6 mm thick hard board backing in circular shape of 450 mm dia.	Nos.	2		
32.	Providing and fixing IS:3564 marked Aluminum die cast body tubular type universal hydraulic door closer with necessary accessories and screws etc. complete.	Each	1.00		
33.	Electrification works including wiring with switches light, fixtures , and exhaust fans—etc.	LS			
34.	Misc. works (such as: Dismantling/ chipping out of old sanitary fittings and fixtures, floor/wall tiles, brick wall etc.)	L.S.			
				Total	

Total amount in words -----

Signature of Contractor with stamp