

Ref: NSIC/Neemka/Civil/Fur./2017-18

Dated -----

M/s

Subject: Quotation for construction of shed at NTSC Neemka (Haryana)

Dear Sir,

Please find enclosed here with Performa for schedule of quantities for the subject work at **NSIC Technical Services Center, Neemka (Faridabad), 121004, under Limited tender enquiry**. The list of eligible bidders are as per Annexure- I. You are requested to quote your competitive rates against items mentioned on schedule enclosed herewith on the terms and conditions given below.

1. Rates should be inclusive of the cost of materials fabrication, labours, fixing, cartage, transportation, scaffolding, other T&P and taxes except GST complete in all respect. GST shall be reimbursed separately to the contractor.
2. Materials of approved quality / make, shade as specified in the schedule shall only be accepted.
3. Payment will be released through NEFT / RTGS after satisfactory completion of the work on actual measurement basis.
4. All statutory deductions as applicable shall be deducted from your payable amount.
5. Work should be completed within 20 days from the date of acceptance of work order. In case work is not completed within schedule time liquidated damage @ 1 % (of the tendered amount) per week or part thereof shall be charged.
6. The defects liability period shall be one year from the date of completion of the work.

7. Earnest money of Rs. 5000/- in the form of Demand draft in favour of **"NSIC-Technical Services Center, Neemka, Faridabad"** payable at Faridabad should be submitted by the bidders along with their offer. Alternatively, EMD may be also paid through RTGS/NEFT as per following details:

Account Name	Bank Name	Bank Account No.	Bank IFSC Code
"NSIC-Technical Services Center, Neemka, Faridabad"	Corporation Bank, Sector-14, Faridabad	124601601000320	CORP0001246

The Bidder is requested to attach the Bank statement/RTGS Slip to provide the transfer of payment to NSIC's account.

8. Earnest money of unsuccessful bidders (Other than the lowest bidder) shall be returned after opening of bids and earnest money of successful bidder shall be retained as security deposit till the defect liability period of one year from the date of completion of the work.
9. **All the bidders are advised to visit the site for assessing the site condition before quoting the rates.**
10. **Offer should reach to this office up to 27th December,2017 by 3.00 PM. Offer shall be opened on the same day at 3.30 PM.**

Thanking you,

Yours faithfully

Rajesh Kumar
Deputy General Manager
Centre Head

Schedule of Quantities

S.no.	DSR item no.	Description of item	Unit	Qty	Rate (Rs.)		Amount (Rs.)
					In figure	In words	
1	2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. for All kinds of soil.	Cum	0.375			
2.	2.27	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	Cum	2.52			

3	4.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:4:8 (1 Cement: 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	Cum	5.346			
4	4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	Cum	3.796			
5	6.13.1	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor level. Cement mortar 1:3 (1 cement :3 coarse sand) sqm 3 coarse sand)	Sqm	8.400			
6.	13.1.2	12 mm cement plaster of mix :1:6 (1 cement: 6 fine sand)	Sqm	17.64			

7.	13.41	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water tinnable priming coat with cement primer	Sqm	17.64			
8	10.16.1	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes.	Kg	856			
9	12.50	Providing and fixing pre-coated galvanised iron profile sheets (size,shape and pitch of corrugation as approved by Engineer-in-charge)0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 micronsepoxy primer on both side of the sheet and polyester top coat 15-18microns. Sheet	sqm	42.77			

		<p>should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 meter or as desired by Engineer-in-charge.</p> <p>The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.</p>					
10	12.21.1	<p>Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement:2 coarse sand : 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design : In 75x75 mm deep chase.</p>	Meter	16			
						Grand Total	

Total Rs. In words-----

Signature of bidder with seal

Annexure- I

The name of parties who are eligible to participate in the Limited tender are :-

1. M/s Samyagya Engineers Pvt. Ltd.
C-594, New Friends Colony
New Delhi-110025
2. M/s R.D. Interiors
150 A, IInd floor Sant Nagar
East of Kailash
New Delhi-110065
3. M/s Prem Construction
210 Masjid Moth NDSE-II
New Delhi-110049
4. M/s Pooja Interiors
51,BMK, Giri Nagar , Kalkaji
New Delhi-110019
5. M/s Team Professional
Consultant & Resource Managers
Plot no. 436, Flat no. 5 , Sector -4
Vaishali , Ghaziabad (UP)
6. M/s Celestial Contractor & Engineers Pvt. Ltd.
RZF13A , Lane No. 41A, SadhNgar-II
Palam colony , New Delhi -110045
- 7 M/s Aastha Enterprises
Plot no. -61-A/3 , Shahdara
Delhi-110095 .
- 8 M/s Dev Dutt Gautam
1280/8, Govindpuri,Kalka Ji
New Delhi-110019.