

SIC /HO/Admn-W/XXV-III/09-11

Dated – 6-7-2011

To,

M/s

Subject: Quotation for renovation of staff canteen at NSIC Ltd., Okhla Industrial Estate, New Delhi -110020.

Please find enclosed here with Performa for schedule of quantities for the subject work at NSIC Bhawan, NSIC Ltd., Okhla Industrial Estate, New Delhi-110020. You are requested to quote your competitive rates against item mentioned on schedule -A enclosed herewith on the terms and conditions given below..

1. Rates should be inclusive of the cost of materials, labours, fixing, cartage, transportation, scaffolding, other T&P and taxes etc. complete in all respect.
2. Materials of approved quality / make, shade as specified in the schedule shall only be accepted.
3. Payment will be released by cheque after satisfactory completion of the work on actual measurement basis.
4. All statutory deductions as applicable shall be deducted from your payable amount.
5. Work should be completed within 20 days from the date of acceptance of work order. In case work is not completed within schedule time liquidated damage @ 0.5 % per week shall be charged.
6. Earnest money of Rs. 5000/- in the form of Demand draft in favour of "National Small Industries Corporation Ltd New Delhi" should be submitted by the bidders along with their offer.
7. Earnest money of unsuccessful bidders (Other than the lowest bidder) shall be returned after opening of bids and earnest money of successful bidder shall be retained as security deposit till the successful completion of the work.
8. All the bidders are advised to visit the site for assessing the site condition before quoting the rates.
9. Offer should reach to this office up to 14th July 2011 by 3.00 PM. Offer shall be opened on the same day at 3.30 PM.

Thanking You.

Yours faithfully

**M.A. Khan
Chief Manager (Works)**

Schedule A**Schedule of quantities**

S. No.	Description of item	Qty	Rate (Rs.)	Amount (Rs.)
1.	Distempering with Oil bond washable distemper of approved brand and manufacture to give an even shade on new work (two or more coats). Including priming coat with cement primer on walls and ceiling of canteen and kitchen.	186.10 Sqm		
2.	Painting with synthetic Enamel paint of approved brand manufacture to give an even shade two or more coat on new work on doors, windows and ventilators.	22.80 Sqm		
3.	P/I of four course waterproofing treatment with bitumen felt over roof consisting of first and third course of blown Bitumen 85/25 or 90/15 conforming to IS: 702 applied hot @ 1.45 kg. per Sqm. of area for each course . Second course of roofing felt type 3 grade (Hessian based self finished bitumen felt) and fourth and final course of stone grit 6 mm and down size or pre- sized gravel spread at 6 cubic diameter per sqm. Including preparation of surface but excluding grating complete with bitumen felt (Hessian based) type 3 grade I conforming to IS 1322.	104.00 Sqm		
4.	Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part I) decorative type. Core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bends and face veneers on both faces of shutter of 35 mm thick including ISI marked stainless steel hinges with necessary screws.	2.88 Sqm		
5.	Providing and fixing of Armstrong false ceiling with sillihouted grid system.	600 Sqft.		
6.	Providing and fixing of light fixtures of 2'x2' size for false ceiling (Bajaj or equivalent make).	4 Nos.		
7.	Dismantling of old gypsum board false ceiling.	600 Sqft.		
8	Supplying, fitting & fixing GI pipes complete with GI fittings clamps including cutting and making good the walls. Concealed pipe including painting with anti corrosive bitumastic cutting chases and making good the walls of 15 mm nominal bore.	8 m.		
9.	Providing and fixing self cleaning trap with screwed down or hinge grating with or without bend arm complete including cutting and making	1 No.		

	good the walls and floors 100mm dia.			
10.	Providing and fixing C.P. Brass angle valve for basin mixture and geyser of approved quality conforming to IS 8931 15 mm nominal bore half turn angle valve (mak) for washbasins as per design & drawing and manufacturer's specifications as approved by Eng	1 No.		
11.	P/f plasticized PVC connection pipes with brass union 45 cm. length 15 mm nominal bore	1 No		
12.	Providing and fixing Angular half turn C.P. Brass bib cock of approved quality conforming to IS 8931 of 15 mm dia.	2 Nos.		
13.	Repair of man hole including cleaning repair and replacement of damaged cover of man hole.	2 Nos.		
14.	Replacement of damaged ceramic floor tiles including dismantling of old damaged tiles.	80 Sqft.		
			Total	

Total Rs. In words: -----

Signature of the bidder with stamp