

SIC/HO/ADMIN-W/XXV-III/03

Dated -14-12-2017

To,

M/s

**Subject: Quotation for extension of existing parking shed at camp office
Ministry of MSME, New Delhi.**

Dear Sir,

Please find enclosed here with Performa for schedule of quantities for the subject work at camp office, Ministry of MSME , Lodhi Estate, New Delhi. You are requested to quote your competitive rates against items mentioned on schedule enclosed herewith on the terms and conditions given below.

1. Rates should be inclusive of the cost of materials fabrication, labours, fixing, cartage, transportation, scaffolding, other T&P and taxes except GST complete in all respect. GST shall be reimbursed separately to the contractor.
2. Materials of approved quality / make, shade as specified in the schedule shall only be accepted.
3. Payment will be released through NEFT / RTGS after satisfactory completion of the work on actual measurement basis.
4. All statutory deductions as applicable shall be deducted from your payable amount.
5. Work should be completed within 10 days from the date of acceptance of work order. In case work is not completed within schedule time liquidated damage @ 1 % (of the tendered amount) per week or part thereof shall be charged.

6. The defects liability period shall be six month from the date of completion of the work.
7. Earnest money of Rs. 2000/- in the form of Demand draft in favour of " The National Small Industries Corporation Ltd" payable at New Delhi should be submitted by the bidders along with their offer.
8. Earnest money of unsuccessful bidders (Other than the lowest bidder) shall be returned after opening of bids and earnest money of successful bidder shall be retained as security deposit till the defect liability period of six month from the date of completion of the work.
9. All the bidders are advised to visit the site for assessing the site condition before quoting the rates.
10. Offer should reach to this office up to 28th December 2017 by 3.00 PM.
Offer shall be opened on the same day at 3.30 PM.

Thanking you.

Yours faithfully

A R Siddiqui
Manager (Works)

Schedule of Quantities

S. no.	DSR item no.	Description of item	Unit	Qty	Rate (Rs.)		Amount (Rs.)
					In figure	In words	
1	2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m..All kinds of soil.	Cum	0.50			
2	4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	Cum	0.50			
3	10.16.1	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting,	Kg	792			

		<p>hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes.</p>					
4	12.50	<p>Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 micron epoxy primer on both side of the sheet and polyester top coat 15-18microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of</p>	Sqm	36			

		purlins, rafters and trusses and including cutting to size and shapewherever required.					
5	13.61.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work . (For steel truss, frame—etc.)	Sqm	36			
						Grand Total	

Total Rs. In words-----

Signature of bidder with seal