ISO 9001: 2000

राष्ट्रीय लघु उद्योग निगम लिमिटेड

THE NATIONAL SMALL INDUSTRIES CORPORATION LTD.

(A GOVERNMENT OF INDIA ENTERPRISE)
"NSIC BHAVAN" OKHLA INDUSTRIAL ESTATE, NEW DELHI-110 020 (INDIA)

SIC /HO/WD/NTSC(O)/5/1(8)/06

Date - 30-4-2010

To.

| NA | /e |
|-----|-----|
| IVI | / 3 |

Subject : Quotation for fabrication & fixing of MS main gate at main entrance of NTSC Okhla :

Please find enclosed here with Performa for schedule of quantities for the subject work at NTSC Okhla, main entry , Okhla Industrial Estate , New Delhi-110020. You are requested to quote your most competitive rates against each item mentioned on schedule enclosed with at the terms and conditions given below.

- 1. Rates should be inclusive of the cost of materials, fabrication labours, fixing, cartage, transportation, scaffolding, other T&P and taxes etc. in all respect.
- 2. Material, of approved quality size /make specified in the enclosed drawing shall only be accepted.
- 3. Payment will be released by cheque after satisfactory completion of the work on actual measurement basis.
- 4. All statuary deductions as applicable shall be deducted from your payable amount.
- Work should be completed within 7 days from the date of acceptance of work order. In case work is not completed within schedule time liquidated damage @ 2% per week shall be charged.
- 6. All the bidders are advised to visit the site for assessing the site condition before quoting the rates.
- 7. Offer should reach to this office up to 10th May 2010 by 3.00 PM. Offers shall be opened on the same day at 3.30 PM.

 Thanking You

Yours faithfully

M.A. Khan

Chief Manager (Works)

"हम हिन्दी में किए गए पत्र—व्यवहार का स्वाग्रामामा के प्राप्त के

Performa

| S. No. | Item | Qty | Rate | Amount |
|--------|--|-----------|--------|--------|
| 1. | Earth work in Excavation for grouting of main pillars | 3.00 Cum. | (Rs.) | (Rs.) |
| 2. | PCC of 1:5:10 (1 Cement: 5 coarse sand: 10 stone aggregate) in base of pillars | 0.25 Cum. | | |
| 3. | Concrete of 1:2:4(1 Cement: 2 coarse sand: 4 stone aggregate) in foundation of pillars | 2.75 Cum. | | |
| 4. | Fabrication and fixing of MS gate of approved design and shape. | 2000 Kg. | | |
| 5. | Painting the MS gate with synthetic Enamel paint two or more coats. | 52 Sqm. | | |
| | | | Total | |

| Total Rs. in words | *************************************** |
|--------------------|---|
| | |

Signature of contractor with stamp