22<sup>nd</sup> Aug., 2008

To,

Μ/	S.	•••	••	•••	•••	•••	•••	•••	•••	•••	••
••••	•••	•••	•••		• •	••	•••	• • •	• •	•••	•••
•••	•••	•••	••		••	••	••	•••	• •	•••	•••

## Sub: Renovation Material Testing Lab., NTSC, Okhla New Delhi-110020.

Dear Sirs / Madam,

Please find enclosed herewith Performa for schedule of quantities for the subject work at NTSC, Okhla, New Delhi -20. You are requested to quote your most competitive rates against each item mentioned in the schedule enclosed herewith on the terms and conditions given below.

## **TERMS & CONDITIONS**

- 1. Rate should be inclusive of cost of all Taxes, Material, Labours, scaffolding and other T & P required for the work.
- 2. The steel design reinforcement duly certified by the structural Engineer is to be submitted by the lowest bidder before the commencement of work.
- 3. Payment will be released by cheque after satisfactory completion of work on actual measurement basis.
- 4. Work shall be completed within 45 days from the date of acceptance of work order.
- 5. The offer should be accompanied with EMD of Rs. 15,000/- by way of DD/Pay order favouring NSIC LTD. A/C NTSC.
- 6. You will be fully responsible for PF & ESI contribution to the concerned authorities for the persons engaged towards execution of above said work.
- 7. Lay out plan for the site is enclosed herewith for the reference.
- 8. Offer should reach to this office on 5th Sept. 2008 by 12:00 Noon and shall be opened at 3:30 p.m on the same day.

Thanking You

Yours faithfully

(P.K.Biswas) GM (NTSC)

## NTSC-OKHLA SCHEDULE OF QUANTITIES FOR MATERIAL TESTING LAB.,NTSC, OKHLA, NEW DELHI.

S.NO.	ITEMS	UNIT	QTY	RATE(RS)	AMT(RS)
1	Demolishing cement conc. Manually/ by mechanical	CU.M	2.00		. ,
	means including disposal of material within 50				
	meters lead as per the direction of engineer -				
	in -charge				
2	Demolishing R.C.C. work Manually/ by mechanical	CU.M	26.88		
	means including disposal of material within 50				
	meters lead as per the direction of engineer				
	-in -charge.				
3	Demolishing brick work Manually/ by mechanical	CU.M	6.00		
-	means including disposal of material within 50				
	meters lead as per the direction of engineer.				
	-in -charge				
4	Dismantling old plaster or skirting racking out joints	SQ.M	235.25		
	and cleaning the surface for plaster including	00.111	200.20		
	disposal50 meters lead as per the direction				
	of Engineers-in-charge.				
5	Reinforcement cement conc. Work in beams,	CU.M	27.00		
5	suspended floors, roofs, having slope of 15 landings,	00.101	21.00		
	balconies, shelves, chajjas, lintels bands,				
	· · · · · · · · · · · · · · · · · · ·				
	plain window sills, staircase and spiral stair case upto the floor five level excluding the cost of centering				
	shuttering, finishing and reinforcement				
	with 1:2:4(1cement: 2 coarce sand: 4graded stone				
	Aggregate 20mm nominal size).				
	Aggregate zonnn nonnnar size).				
6	Contaring and chuttaring including strutting	SO M	226.00		
6	Centering and shuttering including strutting, propping and removal of form for :Suspended floors,	SQ,M	226.00		
	Roofs, landing, balconies and access platform.				
	Roois, landing, balconies and access platform.				
7	Painforcement for D.C.C. work including straightening	KC	2050.00		
7	Reinforcement for R.C.C. work including straightening	KG	3950.00		
	, cutting, bending in position and binding all complete.				
	(i) Cold twisted bars				
		00.14	045.00		
8	6mm cement plaster of mix:1:3(1cement: 3 fine sand)	SQ.M	215.00		
9	Brick work with FPS bricks of class design. 75 in	CU.M	6.00		
	superstructure above plinth level upto floor V level in				
	1:6(1cement: 6 coarse sand)				
10	10cm thick(average) mud phaska of damped brick	SQ.M	200.00		
	earth on roofs laid to slope consolidated & plastered				
	with 25 mm thick mud mortar mixed with bhusa at				
	35kg per cum of earth and gobri leaping with mix				
	1:1(1clay: 1cow dung) and covered with flat tiles				
	bricks of class desig. 100 grouted with cement				
	mortar 1:3(1cement: 3 fine sand) mixed with 2%				
	integral waterproofing compound by weight of				
	cement and finished neat.				
11	Painting top of roofs with approved quality at 17kg	SQ.M	215.00		
	per 10sqm impregnated with a coat of coarse sand at				
	60cudm per 10sqm including cleaning the slab				
	Surfaces with brushes and finally with a piece of cloth				
	lightly soaked in kerosene oil complete:				

12	Providing gola 75mmX75mm in cement conc.1:2:4	RMT	107.00	
	(1cement: 2 coarse sand: 4graded stone aggregate			
	10mm and down gauge) including finished with			
	cement mortar 1:3(1cement: 3 fine sand) as per the			
	standard design.			
14	Making khurras 45X45cm with average minimum	NOS.	10.00	
	thickness of 5cm cement conc.1:2:4(1cement:			
	2 coarse sand: 4graded stone aggregate of 20mm			
	nominal size ).			
15	15 mm cement plaster on rough side of single or	SQ.M	235.25	
	half brick wall finished with a floating coat of neat			
	cement of mix: 1:3(1cement: 3 fine sand)			
16	12 mm cement plaster on rough side of single or	SQ.M	45.00	
	half brick wall finished with a floating coat of neat			
	cement of mix: 1:4(1cement: 4 fine sand).			
17	Distempering with dry distemper of approved brand	SQ.M	952.00	
17	and manufacture(two or more coats) and of required	50.10	952.00	
	shade on new work, over and including priming coat			
	of whiting to give an even shade.			
18	Finishing walls with waterproofing cement paint of	SQ.M	200.00	
10	required shade: New work(Two or more coats applied	00.10	200.00	
	3.84 kg/10sqm.			
19	Painting with synthetic enamel paint of approved brand	SQ.M	33.00	
	and manufacture two or more coats on new work over			
	an under coat of suitable shade with ordinary paint of			
	approved brand and manufacture.			
20	Plastering with chicken wire mesh over the required	SQ.M	10.00	
	places as per the direction of Engineers-in-charge.			
04	Draviding & laving electrical conduits for roof before			
21	Providing & laying electrical conduits for roof before			
	casting the roof slab. All material should be of ISI			
	mark & shall be Laid as per the direction of direction			
	of Engineer-in Charge. TOTAL	L.S.	L.S.	
	IVIAL			

Total amount in words-

Signature of the bidder with seal