

## Offer

SIC/WD/5/1(IV)/98

Date- 25-9-2008

### **Subject- Quotation for modification /repair of Welding Shop at NTSC Okhla**

Please find enclosed herewith Performa for schedule of quantities for the subject work at NTSC Okhla New Delhi. You are requested to quote your most competitive rates against each item mentioned on schedule enclosed with at the terms and conditions given below

#### **Terms and conditions:**

1. Material of approved quality/make and shade shall only be accepted.
2. Rate should be inclusive of the cost of materials, scaffolding, fixing, cartage, transportation labours, other T & P and taxes etc. complete in all respect.
3. Payment will be released by Cheque after satisfactory completion of the work on actual measurement basis. All statutory deductions as applicable shall be deducted from your payable amount.
4. Work shall be completed within Ten days from the date of acceptance of work order. In case work is not completed within schedule time liquidated damages @ 2 % per week shall be charged.
5. All the bidders are advised to visit the site for assessing the site condition before quoting the rates.
6. Offer should reach to this office on 6<sup>th</sup> of October 2008 by 3 PM. Offers shall be opened on the same day at 3.30 PM.

Thanking you,

Yours faithfully

M. .A. Khan  
Chief Manager ( Works)

## Performa

S.no.	Item	Qty	Rate ( Rs.)	Amount ( Rs.
1.	Demolishing brick work manually /by mechanically means including stacking of serviceable material and disposal of unserviceable material within 50 meter lead as per direction of Engineer In-charge in cement mortar.	7 Cum.		
2.	Demolishing RCC manually/by mechanical means including disposal of material within 50 meter lead as per direction of Engineer In-charge	1.06 Cum.		
3.	P/I 1:2:4 ( 1 Cement : 2 Coarse sand : 4 Coarse aggregate ) grade RCC in beam	1.00 Cum.		
4.	MS Steel for RCC	100 Kg.		
5.	Shuttering for beam	6.21 Sqm.		
6.	Half brick work to cover the windows in 1:4 cement coarse sand mortar.	34 Sqm.		
7.	9" thick Brick work in super structure with 1:4 cement coarse sand mortar	3.91 Cum.		
8.	15 mm. Thick Plaster of 1:4 cement fine sand mortar.	60 Sqm.		

9.	Pointing on Brick work from outside with 1:3 cement fine sand mortar.	10 Sqm.		
10.	Synthetic Enamel paint on shutters and windows over a coat of steel primer .	100 Sqm.		
11.	P/f of heavy duty rolling shutter of 80x1.25 MS laths with 1.25 mm. Thick top cover	23 Sqm.		
12.	P/f of ball bearing for rolling shutter	4 Nos.		
13.	Extra for providing mechanic device exceeding 16.80 Sqm. area.	23 Sqm.		
14.	Dismantling of existing shutter	1 No.		
15.	Whitewash with lime on ceiling and walls	600 Sqm.		
16.	Add for extra height. For whitewashing	350 Sqm.		
17.	BRT 6gauge MS jail of size 75mmx25 mm fixed on MS angel frame of size 30x30x5 including welding fixing and applying a priming coat of steel primer.	70 Sqm.		
			<b>Total Rs.</b>	

**Total Rs. (In words)**

**Signature of bidder with stamp**